**TECHNICAL EXHIBIT**

**2018 DISPLACEMENT/FILING WINDOW FOR LPTV AND TV TRANSLATOR STATIONS**

FACILITY: KHDT-LD, FI 168641
DENVER, CO
SYNCOM MEDIA GROUP, INC
Existing FCC file number BLDTL-20111128FOX

Pursuant to the LPTV/Translator displacement/filing window of 2018 arising from the incentive auction 600 MHz TV band repack, the within application is filed to change the facility as follows: change output channel 16 to channel 14, FULL SERVICE mask, 15 kW ERP. Antenna make and model is SCA CL-1469 ARRAY which is to be located on unregistered tower in the midst of Denver tower farm, existing and unchanged at 14.0 m AGL, specified rotation 90°. The facility is being displaced from its channel 16 by repacked KQDK-CD.

NIER is less than 5% of the limit for this service; no new tower construction is planned. Using the specified equipment, pattern and ERP, the application is in compliance with all pertinent portions of §74.793 with respect to all existing part 73 and part 74 licenses, permits and applications known as of the time of filing; however, as a station in the LPTV or TX service which is displaced into the core or otherwise required to modify its facilities in accordance with the presence of an incoming repacked full service station assigned to its previous channel, the within applicant agrees, if necessary, to not operate on the channel or with the service proposed in the within application until any potentially mutually interfering repacked full service station or stations have left their channels pursuant to the relevant phase assignment(s).

J. R. McDonald