TECHNICAL EXHIBIT

2018 DISPLACEMENT/FILING WINDOW FOR LPTV AND TV TRANSLATOR STATIONS

FACILITY: W42EB-D, FI 13637
SYRACUSE, NY
JOHN MESTER INCOME FAMILY TRUST
Existing FCC file number BLDTL-20110622AAA

Pursuant to the LPTV/Translator displacement/filing window of 2018 arising from the incentive auction 600 MHz TV band repack, the within application is filed to change the facility as follows: The facility is being displaced into the core; change output channel 42 to channel 16, FULL SERVICE mask, 12.3 kW ERP. Antenna make and model is PSI PSILP16OI which is to be located on existing equipment tower on building in downtown Syracuse at 107.0 m AGL, rotation 215°.

NIER is less than 5% of the limit for this service; no new tower construction is planned. Using the specified equipment, pattern and ERP, the application is in compliance with all pertinent portions of §74.793 with respect to all existing part 73 and part 74 licenses, permits and applications known as of the time of filing; however, as a station in the LPTV or TX service which is displaced into the core or otherwise required to modify its facilities in accordance with the presence of an incoming repacked full service station assigned to its previous channel, the within applicant agrees, if necessary, to not operate on the channel or with the service proposed in the within application until any potentially mutually interfering repacked full service station or stations have left their channels pursuant to the relevant phase assignment(s).

J. R. McDonald