



J-Crow Tower Works LLC

10170 RD 553

PHILADELPHIA, MS 39350

Phone : 601-656-0039

E-mail:

john@jcrowtower.com

DATE: 02-12-2015

PROPOSAL # 15-020A

STATUS : Labor

CLIENT: Alabama Media, LLC

P.O.Box 4808

Monroe, LA 71211

CONTACT: Bob Holladay

PHONE :

E-m :

SITE: Slocomb, AL

PROPOSED WORK:

Supply crews and equipment for foundation installation. (normal soil)

Supply crews and equipment for installation of tower.

Install additional hardware as listed (page 2)

Install antenna , TX lines and hardware as listed (page 2)

Install light systems (as listed page 2)

Freight (J-Crow supplied equipment – Slocomb, AL site)

CUSTOMER SHALL SUPPLY:

Clear ingress and egress to and about site for crews and equipment.

All required licenses, permits, engineering, taxes, local labor requirements.

Equipment required for on-site deliveries of tower and materials.

Accurate locations for land plot, tower foundations and utilities.

Complete tower steel package, lighting, antenna and materials to site.

PRICE \$ 36,000.00

TERMS: \$ 9,000.00 Deposit on proposal*.

\$ 9,000.00 On completion of foundation installation.

\$ 4,500.00 On delivery of tower sections to site.

\$ 4,500.00 on completion of tower steel erection.

BALANCE ON COMPLETION

*PAYMENT OF DEPOSIT IS ACCEPTANCE OF THIS PROPOSAL AS A CONTRACT.

ADDITIONAL TERMS BY CUSTOMER SHALL BE SUBMITTED FOR APPROVAL BY J-CROW
AND ANY ADDITIONAL COST IS IN ADDITION TO BID. ALL BIDS VALID FOR 30 DAYS.

J-CROW TOWER WORKS LLC
10170 ROAD 553
PHILADELPHIA, MS 39350
601-656-0039

Date: 02-12-2015
Proposal # 15-020A

Loading Requirements : ANSI/TIA-222G

Equipment loading design: [Note : (S/I) , J-Crow supply and install]

1 – SHPX-4AE 4 Bay FM antenna	441' – 411'	3" Flex TX line
1 - PR-950 Parabolic (Dish)antenna	210'	7/8" TX line
1 - A2 Red Beacon kit w/mount	Top	conduit as required
2 - Red Beacon w/mount and ice shield	220'	conduit as required
2 – 3 bulb side light w/mounts	110', 330'	conduit as required
1 Safety climb kit (wo/ harness)	446'	
Single point 5/8" grounding rod system	as required	base / anchors
Wave guide bridge kit w/ hangers	as required	Tower to building

Customer responsible for timely delivery of materials and hardware along with secure storage of it's property during installation. Remob fee charged for lack of required materials and hardware resulting in delays in construction.

Submitted by: J-Crow Tower Works LLC

John Morrow
Manager