

[Exhibit 13]

Non-Interference Compliance

Regarding Facility id 145113

Channel 229

Description of Exhibit 13 Contents

This exhibit demonstrates that the proposed facility complies with contour overlap and interference protection provisions in all of the applicable rule sections and that this application for a construction permit is in full compliance with 47 C.F.R. § 74.1204.

Let it be noted that should any actual real world interference occur, the applicant acknowledges that it will promptly suspend operation of this translator in accordance with 47 C.F.R. § 74.1203.

Page 2 of this exhibit is an explanation of the method used to demonstrate compliance with contour overlap and interference provisions based on 47 C.F.R. § 74.1204(d), which states:

[A]n application otherwise precluded by this section will be accepted if it can be demonstrated that no actual interference will occur due to intervening terrain, lack of population or such other factors as may be applicable.

Page 3 of this exhibit contains the tabulated data from the interference analysis, which shows all stations whose protected contours come within 50 km of the 34 dB μ F(50,10) contour of the proposed translator. These tabulated values were calculated using data from the FCC's CDBS files and 30 arc second terrain data. The column labeled "Adj" shows the number of channels difference between the entry and the proposed translator. The column labeled "Dist" shows the distance in km. The column labeled "Overlap" shows the area of contour overlap in square kilometers.

Page 4 of this exhibit is a portion of a USGS 1:24,000 scale 7.5 minute quadrangle at full scale with the calculated area of interference overlaid. The sheet includes the quadrangle name and measurement scale at the bottom-left corner (note: "Mt" refers to meters). The area of interference was calculated using the free space equation and 120 radials.

Compliance with 47 C.F.R. § 74.1204(d)

All authorized second and third adjacent stations with which the proposed translator has contour overlap are tabulated below. Column four show the station's signal level at the proposed translator's tower site, and column five gives the minimum value within the entire standard interfering contour of the proposed translator (100 dB μ for most classes, 94 for class B, 97 for class B1). The minimum second or third adjacent F(50,50) contour within the proposed translator's standard interfering contour was used to calculate the proposed translator's actual "worst-case" interfering contour.

Application_id	File Number	Callsign	Contour at Tower	Min. Contour
1097380	BLH20051201CGX	WEAS-FM	86.6	86.3
604356	BLH20020604AAV	WQBT	89.2	88.9
Minimum F(50,50) Contour of Adjacent Station within Proposed Translator's Standard Interfering Contour				86.3

FCC 02-244 at Section II.A.5 states that "when demonstrating that 'no actual interference will occur due to . . . other factors,' pursuant to Section 74.1204(d), an applicant may use the undesired-to-desired signal ratio method." The undesired-to-desired ratio for second and third adjacent stations required by § 74.1204(a) is 40 dB. Since the minimum protected contour strength within the proposed translator's standard interference contour is **86.3 dB μ** , this makes the proposed translator's worst-case interfering contour **126.3 dB μ** . By the free-space equation, this contour is calculated to extend a maximum of **14.8 m** from the transmit antenna.

The interfering contour of the proposed translator was calculated for 120 radials and plotted on the pertinent portion of a USGS quadrangle (page 4 of this exhibit). As demonstrated on the quadrangle, there are no populated structures or highways within the area of interference (Note: FCC 02-244 at Section II.A.6 states that USGS quadrangles "have been recognized as acceptable to demonstrate lack of population"). Hence, in accordance with 47 C.F.R. § 74.1204(d) and the clarification provided by the FCC in the decision *Re: Living Way Ministries* (FCC 02-244), a lack of population has been demonstrated within the area of interference and this application is therefore in full compliance with 47 C.F.R. § 74.1204.

Antenna Manufacturer: NIC
Antenna Model: BKG77
CORAGL: 89 m
Maximum ERP: 0.019 kW
Interfering Contour: 126.3 dB μ
Max Int. Contour Distance: 14.8 m

**Adjacent Channel Study
For Station W229AJ, Facility_id: 145113**


Co-channel through third adjacent:

Application_id	Facility_id	Prefix	ARN	Call	Licensee	Class	City	State	Status	ERP	RCAMSL	Channel	Adj	Dist	Overlap
1097380	71366	BLH	20051201CGX	WEAS-FM	CUMULUS LICENSING LLC	C1	SPRINGFIELD	GA	LIC	96.64	303.7	226	3	21.4	0.1134
604356	8594	BLH	20020604AAV	WQBT	CAPSTAR TX LLC	C0	SAVANNAH	GA	LIC	100	402	231	2	21.4	0.1134
601228	8594	BXLH	20020322ABU	WQBT	CAPSTAR TX LLC	C0	SAVANNAH	GA	LIC	12	64	231	2	37.2	0
637653	145130	BNPFT	20030317DNS	NEW	RADIO ASSIST MINISTRY, INC.	D	SAVANNAH	GA	APP	0.01	152.9	229	0	40.5	0
191679	24620	BLH	19931108KA	WDOG-FM	GOOD RADIO BROADCASTING, INC.	A	ALLENDALE	SC	LIC	6	146	228	1	99.8	0
561643	30658	BLH	20010502AAV	WVOH-FM	BROADCAST SOUTH, LLC	C3	HAZLEHURST	GA	LIC	25	157	228	1	102.3	0
1323169	30658	BPH	20081030ACZ	WVOH-FM	BROADCAST SOUTH, LLC	C2	NICHOLLS	GA	CP	40	221.1	228	1	125.9	0
1404157	30658	BMPH	20101102ABT	WVOH-FM	BROADCAST SOUTH, LLC	C2	NICHOLLS	GA	APP	50	198.2	228	1	131.3	0



Facility id: 145113;
Area of Interference;


(LETFORD) 4648 II SE 48 32'30" 150 INTERIOR—GEOLOGICAL SURVEY, RESTON, VIRGINIA—1977



VERTICAL INTERVAL 10 FEET
MEAN SEA LEVEL VERTICAL DATUM OF 1929



QUADRANGLE LOCATION



NATIONAL MAP ACCURACY STANDARDS
GEOLOGICAL SURVEY, RESTON, VIRGINIA 22092
MAPS AND SYMBOLS IS AVAILABLE ON REQUEST