

# Federal Communications Commission

## DISTRIBUTED TRANSMISSION SYSTEM CONSTRUCTION PERMIT

**Licensee/Permittee**

LONG COMMUNICATIONS, LLC.  
526 MAIN AVENUE SE  
HICKORY, NC, 28602

<b>Call Sign</b>	<b>File Number</b>
WHKY-TV	0000024614

**Facility ID:** 65919**NTSC TSID:** 1830**Digital TSID:** 1831**This Permit Modifies License File No.:** BLCDT-20110927ACZ

<b>Grant Date</b> 06/02/2017		<b>Expiration Date</b> 10/18/2019
<b>Hours of Operation</b> Unlimited		
<b>Station Location</b>  City HICKORY State NC	<b>Frequency (MHz)</b> 470.0 - 476.0	<b>Station Channel</b> 14
<b>Antenna Reference Coordinates</b>  Latitude 9999 35-43-59.4 N Longitude 81-19-50.3 W		<b>Facility Type</b> Commercial

**DTS Site Number:1**

<b>Antenna Structure Registration Number</b>	
<b>Transmitter</b> Type Accepted. See Sections 73.1660, 73.1665 and 73.1670 of the Commission's Rules.	<b>Transmitter Output Power(kW)</b> As required to achieve authorized ERP.
<b>Antenna Coordinates</b>  Latitude 35-39-28.5 N Longitude 81-24-23.3 W	<b>Antenna Type</b> Directional
<b>Description of Antenna</b>  Make ERI Model ATW18HS3-HTWC-14H	

<b>Antenna Beam Tilt (Degrees Electrical)</b> 0.75	<b>Antenna Beam Tilt (Degrees Mechanical @ Degrees Azimuth)</b> Not Applicable
<b>Major Lobe Directions</b> 125.0 275.0	<b>Maximum Effective Radiated Power (Average)</b> 537 kW 27.30 DBK
<b>Height of Radiated Center Above Ground (Meters)</b> 50	<b>Height of Radiated Center Above Mean Sea Level (Meters)</b> 581
<b>Height of Radiated Center Above Average Terrain (Meters)</b> 251	<b>Overall Height of Antenna Structure Above Ground (Meters)</b> 58

## DTS Site Number:2

<b>Antenna Structure Registration Number</b> 1005065	
<b>Transmitter</b> Type Accepted. See Sections 73.1660, 73.1665 and 73.1670 of the Commission's Rules.	<b>Transmitter Output Power(kW)</b> As required to achieve authorized ERP.
<b>Antenna Coordinates</b>  <b>Latitude</b> 35-17-15.0 N <b>Longitude</b> 80-41-44.0 W	<b>Antenna Type</b> Directional
<b>Description of Antenna</b>  <b>Make</b> ERI <b>Model</b> ALP8L4-HSBR-14	
<b>Antenna Beam Tilt (Degrees Electrical)</b> 1	<b>Antenna Beam Tilt (Degrees Mechanical @ Degrees Azimuth)</b> Not Applicable
<b>Major Lobe Directions</b> 15.0 145.0	<b>Maximum Effective Radiated Power (Average)</b> 10.2 kW 10.09 DBK
<b>Height of Radiated Center Above Ground (Meters)</b> 152	<b>Height of Radiated Center Above Mean Sea Level (Meters)</b> 370.0
<b>Height of Radiated Center Above Average Terrain (Meters)</b> 167	<b>Overall Height of Antenna Structure Above Ground (Meters)</b> See the registration for this antenna structure.

## Waivers/Special Conditions

- During equipment tests, authorized by Section 73.1610 of the Commissions Rules, the permittee shall take adequate measures to identify and substantially eliminate objectionable interference which may be caused to existing land mobile radio facilities in the 460 to 470 MHz band. Documentation that objectionable interference will not be caused to existing land mobile radio facilities shall be submitted along with the request for Program Test Authority. Program tests shall not be commenced under Section 73.1620(a) of the Commissions Rules and may only be started after specific authority is granted by the Commission. An application for a license must be filed within 10 days after the start of program tests.
- The grant of this construction permit is subject to the condition that, with ample time before commencing operation, you make a good faith effort to identify and notify health care facilities (e.g., hospitals, nursing homes, see 47 CFR 15.242(a)(1)) within your service area potentially affected by your DTV operations. Contact with state and/or local hospital associations and local governmental health care licensing authorities may prove helpful in this process. During this pre-broadcast period, you must provide all notified entities with relevant technical details of your operation, such as DTV channel, targeted on-air date, effective radiated power, antenna location, and antenna height. You are required to place in the stations public inspection file documentation of the notifications and contacts made and you may not commence operations until good faith efforts have been made to notify affected health care facilities. During this pre-broadcast period and for up to twenty (20) days after commencing operations, should you become aware of any instances of medical devices malfunctioning or that such devices are likely to malfunction due to your DTV operations, you must cooperate with the health care facility so that it is afforded a reasonable opportunity to resolve the interference problem. At such time as all provisions of this condition have been fulfilled, and either upon the expiration of twenty (20) days following commencement of operations or when all known interference problems have been resolved, whichever is later, this condition lapses.

Subject to the provisions of the Communications Act of 1934, as amended, subsequent acts and treaties, and all regulations heretofore or hereafter made by this Commission, and further subject to the conditions set forth in this permit, the permittee is hereby authorized to construct the radio transmitting apparatus herein described. Installation and adjustment of equipment not specifically set forth herein shall be in accordance with representations contained in the permittee's application for construction permit except for such modifications as are presently permitted, without application, by the Commission's Rules.

Equipment and program tests shall be conducted only pursuant to Sections 73.1610 and 73.1620 of the Commission's Rules.