Federal Communications Commission

TELEVISION BROADCAST STATION CONSTRUCTION PERMIT

Licensee/Permittee
NEXSTAR INC.
545 E. JOHN CARPENTER FREEWAY
SUITE 700
IRVING, TX, 75062

Call Sign	File Number
WSYR-TV	0000127611

Facility ID: 73113
NTSC TSID: 2204
Digital TSID: 2205
This Permit Modifies License File No. BLCDT-20030812ABK

Grant Date	Expiration Date
04/29/2021	36 months after the grant date

Hours of Operation
Unlimited

Station Location	Frequency (MHz)	Station Channel
City SYRACUSE **State** NY	488.0 - 494.0	17

Facility Type
Commercial

Antenna Structure Registration Number
1004101

Transmitter	Transmitter Output Power(kW)
Type Accepted. See Sections 73.1660, 73.1665 and 73.1670 of the Commission's Rules.	As required to achieve authorized ERP.
Antenna Coordinates **Latitude** 42-56-42.0 N **Longitude** 76-1-27.0 W	**Antenna Type** Directional

Description of Antenna
Make AND
Model ALP16M2-HSOC-17

Antenna Beam Tilt (Degrees Electrical) 0.5	**Antenna Beam Tilt (Degrees Mechanical @ Degrees Azimuth)** Not Applicable
Major Lobe Directions 0.0	**Maximum Effective Radiated Power (Average)** 285 kW 24.55 DBK
Height of Radiated Center Above Ground (Meters) 224	**Height of Radiated Center Above Mean Sea Level (Meters)** 707.1
Height of Radiated Center Above Average Terrain (Meters) 402	**Overall Height of Antenna Structure Above Ground (Meters)** See the registration for this antenna structure.

Waivers/Special Conditions

- The grant of this construction permit is subject to the condition that, with ample time before commencing operation, you make a good faith effort to identify and notify health care facilities (e.g., hospitals, nursing homes, see 47 CFR 15.242(a)(1)) within your service area potentially affected by your DTV operations. Contact with state and/or local hospital associations and local governmental health care licensing authorities may prove helpful in this process. During this pre-broadcast period, you must provide all notified entities with relevant technical details of your operation, such as DTV channel, targeted on-air date, effective radiated power, antenna location, and antenna height. You are required to place in the stations public inspection file documentation of the notifications and contacts made and you may not commence operations until good faith efforts have been made to notify affected health care facilities. During this pre-broadcast period and for up to twenty (20) days after commencing operations, should you become aware of any instances of medical devices malfunctioning or that such devices are likely to malfunction due to your DTV operations, you must cooperate with the health care facility so that it is afforded a reasonable opportunity to resolve the interference problem. At such time as all provisions of this condition have been fulfilled, and either upon the expiration of twenty (20) days following commencement of operations or when all known interference problems have been resolved, whichever is later, this condition lapses.

Subject to the provisions of the Communications Act of 1934, as amended, subsequent acts and treaties, and all regulations heretofore or hereafter made by this Commission, and further subject to the conditions set forth in this permit, the permittee is hereby authorized to construct the radio transmitting apparatus herein described. Installation and adjustment of equipment not specifically set forth herein shall be in accordance with representations contained in the permittee's application for construction permit except for such modifications as are presently permitted, without application, by the Commission's Rules.

Equipment and program tests shall be conducted only pursuant to Sections 73.1610 and 73.1620 of the Commission's Rules.