Federal Communications Commission

CLASS A BROADCAST STATION CONSTRUCTION PERMIT

Licensee/Permittee
WTVX LICENSEE, LLC
10706 Beaver Dam Road
Cockeysville, MD, 21030

Call Sign	File Number
WTCN-CD	0000033632

Facility ID: 70865
NTSC TSID: 9284
Digital TSID: 9285
This Permit Modifies License File No.: 0000027427

Grant Date	Expiration Date
11/09/2017	04/12/2019

Hours of Operation
Unlimited

Station Location	Frequency (MHz)	Station Channel
City PALM BEACH **State** FL	488.0 - 494.0	17

Antenna Structure Registration Number
1018573

Transmitter	Transmitter Output Power(kW)
Type Accepted. See Sections 74.750 of the Commission's Rules.	As required to achieve authorized ERP.
Antenna Coordinates **Latitude** 27-1-32.0 N **Longitude** 80-10-41.9 W	**Antenna Type** Non-Directional
Description of Antenna **Make** DIELECTRIC **Model** TLP-12A/VP-R BB	**Major Lobe Directions** N/A
Antenna Beam Tilt (Degrees Electrical) 2	**Antenna Beam Tilt (Degrees Mechanical @ Degrees Azimuth)** Not Applicable

Maximum Effective Radiated Power (Average) 15 kW 11.76 DBK	
Height of Radiated Center Above Ground (Meters) 292	**Height of Radiated Center Above Mean Sea Level (Meters)** 296.9
Out-Of-Channel Emission Mask Full Service	**Overall Height of Antenna Structure Above Ground (Meters)** See the registration for this antenna structure.

Waivers/Special Conditions

- The grant of this construction permit is subject to the condition that, with ample time before commencing operation, you make a good faith effort to identify and notify health care facilities (e.g., hospitals, nursing homes, see 47 CFR 15.242(a)(1)) within your service area potentially affected by your DTV operations. Contact with state and/or local hospital associations and local governmental health care licensing authorities may prove helpful in this process. During this pre-broadcast period, you must provide all notified entities with relevant technical details of your operation, such as DTV channel, targeted on-air date, effective radiated power, antenna location, and antenna height. You are required to place in the stations public inspection file documentation of the notifications and contacts made and you may not commence operations until good faith efforts have been made to notify affected health care facilities. During this pre-broadcast period and for up to twenty (20) days after commencing operations, should you become aware of any instances of medical devices malfunctioning or that such devices are likely to malfunction due to your DTV operations, you must cooperate with the health care facility so that it is afforded a reasonable opportunity to resolve the interference problem. At such time as all provisions of this condition have been fulfilled, and either upon the expiration of twenty (20) days following commencement of operations or when all known interference problems have been resolved, whichever is later, this condition lapses.

Subject to the provisions of the Communications Act of 1934, as amended, subsequent acts and treaties, and all regulations heretofore or hereafter made by this Commission, and further subject to the conditions set forth in this permit, the permittee is hereby authorized to construct the radio transmitting apparatus herein described. Installation and adjustment of equipment not specifically set forth herein shall be in accordance with representations contained in the permittee's application for construction permit except for such modifications as are presently permitted, without application, by the Commission's Rules.

Equipment and program tests shall be conducted only pursuant to Sections 73.1610 and 73.1620 of the Commission's Rules.